Ardwick Train Care Depot



Ardwick Train Care Depot





SPENCER British Engineering

"The project saw the electrification of the existing depot to facilitate the maintenance of electric trains"



SIEMENS OPERATED DEPOT



VALUE **£1.2M**






od-Trak were contracted to supply and install all OLE required to electrify the Siemens operated depot at Ardwick in Manchester.

The existing track layout was a single connection from the Up East line to the single Ardwick Reception Siding, which provides the connection to the facility.

This arrival line was wired to enable the passage of electric rolling stock into Ardwick Train Care Depot from Manchester Piccadilly.

The OLE System was MKIIIB fixed tension. The depot was electrically sectioned which provided various stabling options to the train operator. Road 8 in the maintenance shed was also electrified and tied into the depot Interlocking Protection System.

With careful planning and communication between Pod-Trak, Spencer Group and Siemens, the Depot remained operational throughout the installation programme.



Beddington Lane & Wimbledon Platform 10



Beddington Lane & Wimbledon Platform 10







"Mitcham
Junction to
Beddington
Lane twin
tracking &
Wimbledon
platform 10
extension"



PILING
MAIN STEEL
SPS
WIRING
REGISTRATION



VALUE £1M







od-Trak were contracted by Cleshar Contract Services
Ltd to install a new overhead line system between Mitcham junction and Beddington Lane.
The line was previously a single line which was being upgraded to a twin tracked system.

At Wimbledon Station the existing platform was extended to allow two trams to be stabled on the platform, and a new second platform to be built with an extended line.

Pod-Trak's scope of works at Beddington Lane included 21 piled foundations, 14 new OLE structures, four cantilevers, 12 twin-tack cantilevers, the removal of redundant structures, the transfer of existing OLE to new structures, the running of new OLE twin contact conductors and the registration works.

At Wimbledon Station the works included the removal of redundant OLE structures and wire, the installation of 7 new OLE structures, 200m of new twin contact, new switches and section prove the new lines. This project was driven by a very tight programme to allow commissioning and handover of the new system. All works were planned and delivered within the timescales required, and were successfully handed over after meeting the client's technical requirements.

Craigentinny Depot



Craigentinny Depot



RAILWAY ELECTRIFICATION

SPENCER British Engineering

"The project delivered improvements to Edinburgh's Craigentinny depot to enable maintenance of the Hitachi bi-mode fleet"



OPERATED BY HITACHI RAIL EUROPE



VALUE £500K



RAILWAY ELECTRIFICATION

The project required OLE modifications to facilitate the installation of a new train wash. Works included the installation of new structures, SPS, headspans, section insulators, wiring and registration.

Redundant OLE was stripped out and returned to the maintainer.

Works were carefully planned with Spencer Group and other subcontractors on site to ensure safe delivery of the planned works.

Following completion of the installation and removal works the OLE testing and commissioning successfully took place and handback documentation was completed and returned.



Doncaster Carr Approach



Doncaster Carr Approach






CIVIL ENGINEERING

SPENCER
British Engineering

"Connecting the new Doncaster Carr Depot to the East Coast Main Line"



FOUNDATIONS
STEELWORK
BALANCE WEIGHTS
SWITCHING



VALUE £350K







The works were carried out to electrically connect the newly constructed Doncaster Carr Depot to the East Coast Main Line and along with new OLE construction it included alterations to existing.

A total of ten in-site concrete foundations were installed to support seven OLE structures and three anchors. Works continued with the installation of SPS, registration equipment and 250m of MKIIIB 107mm2 contact and AWAC catenary. The scope also included the installation of a high-speed Arthur Flury section insulator and Morris Line 3 position switch.

Works were successfully completed, section proved and handed back with all necessary handback documentation.



Elmers End Loop – Croydon Tramlink




Elmers End Loop – Croydon Tramlink







"Conversion of an existing siding to a new passing loop"



MAIN STEEL
SPS
WIRING
REGISTRATION
TEST &
COMMISSION



VALUE £150K







At Elmers End on the Croydon Tramlink an existing siding was converted to a passing loop.

Pod-Trak undertook the OLE installation works which included

new structures, SPS and wiring along with alterations to existing infrastructure.

Prior to any trams using the new line, all handover checks were completed including panning and height and stagger recordings. Finally the new installation was tested and commissioned by Pod-Trak prior to entry into service.

Gospel Oak to Barking Electrification



Gospel Oak to Barking Electrification



RAILWAY ELECTRIFICATION

Balfour Beatty

"All resources and plant were supplied inhouse, providing flexibility, experience and reliability"



26 WIRE RUNS
234 SPS LOCATIONS
SWITCHING



VALUE **£2.7M**



RAILWAY ELECTRIFICATION



Pod-Trak undertook the electrification of the Eastern half of the Gospel Oak to Barking route on behalf of Balfour Beatty. The electrification of the lines was undertaken by Network Rail as part of their London Railway Upgrade Plan which doubles the capacity on the line and improves the air quality of those who live and work near the railway.

The GOB electrification uses Series 2 and Furrer+Frey OLE equipment, however the route interfaced with UK1 and OLEMI equipment ranges. Working with a broad range of equipment requires experienced and adaptable staff, which Pod-Trak were able to provide.

The scope consisted of new OLE installation, including main steel, small part steel, wiring, switching, bonding and final registration.
All works were fully assured by our construction and engineering teams backed up by signed quality check sheets and ITP's.

All construction activities were completed through blockades and weekend possessions, which required careful and considered planning to ensure safe and efficient delivery. On completion of the construction and assurance

activities, the route was panned with Pod-Trak's plant as final confirmation that the OLE was fit for the passage of electric trains.

Prior to our mobilisation, the project had been running for two years and had been criticised by the media as another delayed electrification programme.
Following the Balfour Beatty and Pod-Trak mobilisation in summer 2017 and an intense period of site activity the project was successfully energised during the Christmas 2017 blockade. This was shortly followed by the pantograph ready milestone achieved in early in January 2018.

Leighton Buzzard Station AFA




Leighton Buzzard Station AFA





SPENCER British Engineering

"AFA –
improving
access for all at
stations across
Bedfordshire"



FOUNDATIONS
MAIN STEEL
SPS
WIRE RE-PROFILING
REGISTRATION



VALUE £200K



RAILWAY ELECTRIFICATION

A s part of the AFA (Access for All) modifications at Leighton Buzzard Station, a new walkway bridge over the West Coast Main Line was installed across four tracks to provide access to all platforms.

To facilitate these works, Pod-Trak were subcontracted to design, supply and install new foundations, structures, SPS, headspans, wire splicing and re-profiling of the OLE through the bridge.

All works were carried out during possession/ isolation periods and necessary arrangements were put in place to protect the public during foundation installation.



Manchester Metrolink Substations



Manchester Metrolink Substations



RAILWAY ELECTRIFICATION

CIVIL ENGINEERING



"New substations on the Bury & Altrincham lines"



DESIGN
CIVILS SCOPE
OLE SCOPE



VALUE £700K





CIVIL ENGINEERING



To cope with the electrical demands of increased traffic on both the Altrincham and Bury lines, a new substation was built on each line to provide additional power for the Trams.

Pod-Trak carried out a multi-discipline scope at each site by completing the design and installation of both the Civils and OLE at Brooklands on the Altrincham Line and Whitefield's on the Bury Line. The new substations were located within existing car parks. Careful planning and consideration had to be taken daily for the public who were using the station.

The installation works were similar at each site and included piling, substation bases, DNO bases, OLE bases, buried duct routes, UTX's, trough routes,

fencing, paving, Armco barrier, bollard installation and landscaping on Civils.

OLE scope consisted of steel installation, section insulators, GMI installation, bypass isolators, HV feeds, impedance bonding and section proving.

Compound works were all carried out on days while trackside works were delivered over a series of weekend disruptive possessions and midweek engineering hours. OLE foundations were precast at the depot and installed on site with OTP to assist with time constraints.

Manchester Metrolink Phase 3 OLE



Manchester Metrolink Phase 3 OLE







"Electrification of the new Phase 3 extensions across Greater Manchester"



61KM TWIN TRACK ELECTRIFICATION



VALUE **£8.2M**







Co to install all of the overhead line equipment (OLE) including Traction Power on the Phase 3 extensions to the Manchester Metrolink.

This links the City Centre to Manchester Airport, Didsbury, Ashton, Media City, Oldham, Rochdale and the new tram depot at Trafford.

Works included tying the new OLE into the existing phase 1 and 2 lines over a series of disruptive possessions, and the construction of new OLE over the new track bed.

The Tramway OLE was varied in its construction, ranging from autotensioned traditional catenary systems over segregated areas, to fixed termination trolley wire systems within the public areas. The extensions included many complex OLE layouts over road junctions and pedestrianised areas.

The overhead line works were the largest ever undertaken in a UK light rail environment.

North West Electrification (NWEP) Phase 2




North West Electrification (NWEP) Phase 2



RAILWAY ELECTRIFICATION

Balfour Beatty

"New electrification on Phase 2a, 2b and 2c of the North West Electrification Project"



SERIES 2
OVERHEAD
LINE EQUIPMENT



VALUE **£1.8M**




RAILWAY ELECTRIFICATION

Pod-Trak were approached by Balfour Beatty Rail in July 2014 to assist with the installation of new OLE on the Liverpool to Manchester and Liverpool to Wigan routes.

The series 2 equipment was supplied free issue by BBR and installed by Pod-Trak teams working on our RRV MEWPs.

Core works included SPS installation, wiring and final registration.

Critical tie-ins to existing electrification at Edge Hill and the West Coast Mainline were all carried out by Pod-trak. All plant moves between sites were managed and carried out in-house.



Sandy Station Bedfordshire




Sandy Station Bedfordshire





SPENCER British Engineering

"Following two years" experience on light rail this was Pod-Trak's first OLE project on Network Rail infrastructure"



MAIN STEEL

NEW HEADSPANS

REGISTRATION

REDUNDANT REMOVALS



VALUE £100K




RAILWAY ELECTRIFICATION

The main contract works were carried out by Spencer Group to extend the platforms at Sandy Station in Bedfordshire on the East Coast Mainline. Pod-Trak were subcontracted to carry out all the OLE works necessary to facilitate the platform extensions.

The existing masts on the up slow had to be removed and new masts installed one meter along the track. Both headspans had to be transferred to the new masts while retaining the existing heights and staggers across all four lines.

All works were successfully completed and handed back on time. This was the first OLE project Pod-Trak carried out on Network Rail Infrastructure after many years on light rail projects.



Swansea Maliphant Intercity Express Depot (Hitachi)




Swansea Maliphant Intercity Express Depot (Hitachi)





VolkerFitzpatrick

"South Wales main line depot operated by Hitachi Rail Europe"



MAIN STEEL
SPS
SWITCHING
HEADSPANS



VALUE £750K



RAILWAY ELECTRIFICATION

od-Trak were contracted to supply and install all the OLE required to electrify the Hitachi-operated depot at Swansea. Works included the supply and installation of transfer plates, structures, SPS, headspans, switching and bonding.

The installation of the contact wire was omitted from the scope to reduce the risk of theft, as the depot will not go live until the Great Western Electrification reaches Swansea. Works also included the installation of structures along the NWR main line. With careful planning and communication between Pod-Trak, the client and Hitachi, the depot remained operational throughout the installation programme.

In 2018 Pod-Trak returned to site to remove the SPS as it is now unlikely that electrification will reach Swansea.



Swansea Depot Civils



Swansea Depot Civils



CIVIL ENGINEERING



"Depot remodelling to facilitate the re-fuelling of bi-mode trains."







VALUE £1.5M



CIVIL ENGINEERING

nod-Trak were contracted to carry out all the civils modifications within the depot that were necessary to facilitate the maintenance and use of bi-mode trains being used on the Great Western Main Line.

The scope of works included UTX's, drainage, walkways, HV cable routes, concrete bases, a new layby and retaining structures. All works were carried out on midweek days with careful planning to ensure the depot remained operational at all times.

Deep excavations with poor ground conditions throughout the depot posed a constant challenge to the project team. Temporary works design and controls were key to making sure our teams and others within the depot were not put in any danger during the construction phase.

Works were facilitated by the use of in-house on track plant to move materials through the depot on a daily basis.

