

Elmers End Loop – Croydon Tramlink



*“Conversion
of an existing
siding to a new
passing loop”*



Contact wire installation

MAIN STEEL
SPS
WIRING
REGISTRATION
TEST &
COMMISSION



MAY 2012 -
JULY 2012

VALUE
£150K

LONDON



Elmers End Loop – Croydon Tramlink



Croydon tram

At Elmers End on the Croydon Tramlink an existing siding was converted to a passing loop.

Pod-Trak undertook the OLE installation works which included

new structures, SPS and wiring along with alterations to existing infrastructure.

Prior to any trams using the new line, all handover checks were completed including panning and

height and stagger recordings. Finally the new installation was tested and commissioned by Pod-Trak prior to entry into service.