

Silwood Depot Sidings



Silwood Depot Sidings



“Provision of new driver walkways with lighting across the new sidings with support from ETE teams for conductor rail adjustments”



New driver walkways

Pod-Trak undertook a challenging role in this project to deliver a civils package with large programme and logistical constraints.

An ever-changing P-Way design required tactical installation of the ensuing civils element of the project, with very little re-work or re-visits required by our team.

The walkways consisted of reinforced concrete with ducting and sleeves installed for the lighting columns. Along side the walkways a concrete cable trough was laid for cable management.

The great dedication from our workforce also contributed to Pod-Trak gaining additional scope by being awarded a contract to provide ETE support to complement Cleshar's electrification works in the sidings



Concrete walkways and cable route

**LIVE
DEPOT
WORKING**



**FEB 2014
- SEP 2014**

**VALUE
£800k**



LONDON